

<p>PERCH LAKE TOWNSHIP 2779 Big Lake Road, Cloquet, MN 55720</p>		<p><i>Gary Harms, Chair Keith Depre, Supervisor Steve Olson, Supervisor Cheri DeMenge, Treasurer Lora Eames, Clerk</i></p>
<p>perchlaketownship@gmail.com perchlaketownship.org 218-391-9178 (Clerk)</p>		

REQUEST FOR QUOTES
CRACKPATCHING & CRACKSEALING PAVED ROADS IN
PERCH LAKE TOWNSHIP

The Perch Lake Township Board of Supervisors is requesting quotes for the patching and sealing of cracks on some paved roads in Perch Lake Township.

I. GENERAL INFORMATION:

- a. The Township Board of Supervisors will determine which roads will be crackpatched and sealed.
- b. The successful Contractor will:
 - Crack patch and fill holes and bad cracks as needed. (**SEE SPECIFICATIONS ON PAGE 2.**)
 - If quote deviates from specification Contract must provide specifications used.
 - Supply all equipment, labor, and materials.
 - Be required to provide an insurance certificate verifying general liability insurance, a minimum of \$1.5 million per occurrence. (This insurance must cover all equipment operated for the work.)
 - Have a Tax ID No. (Federal Employer Identification or Social Security No.).
 - Workers compensation insurance if required, under Minnesota state law.
 - Be willing to sign "Indemnification, Hold Harmless and Defend Document" if quote is accepted.
 - The work must be completed no later than September 30, 2019.
- c. Contact for questions: Road Supervisor Supervisor Steve Olson at (218-591-1795).

II. PROCESS:

- a. Quotes must be signed.
- b. Quotes can be mailed or emailed to the address below at Perch Lake Town Hall to Clerk Lora Eames by 7:00 p.m. on Monday, June 10, 2019, before the regular monthly meeting of the Perch Lake Town Board.

SEND QUOTATION TO

Perch Lake Township, Attention Clerk Lora Eames
2779 Big Lake Road, Cloquet, MN 55720
perchlaketownship@gmail.com or

- c. Supervisors reserve the right to delay a decision, negotiate with contractors regarding their proposals, or reject any and all quotes. The lowest quote will not be the only basis for consideration.

III. SPECIFICATIONS & PROPOSED COSTS:

NEW CRACKS ¼" to ¾" wide Router 3/4" x 3/4" using a router machine.
 Blow out and heat lance for sterilization of cracks for proper bonding.
 Fill with MN DOT approved 3723 hot rubberized sealant.
 Paper barrier.

PREVIOUSLY FILLED CRACKS Clean and fill.
 Blow out and heat lance for sterilization of cracks for proper bonding.
 Fill with MN DOT approved 3723 hot rubberized sealant.
 Paper barrier.
 Repair of damaged asphalt sections. Spray patching.

SPRAY PATCHING for cracks greater than ¾" wide or pothole. Asphalt emulsion, aggregate, and high-volume air allow an operator to clean, tack, and patch potholes quickly and easily. A spray patch injection machine manufactured for this purpose uses high volume air to blow out loose debris followed by asphalt emulsion tack. The aggregate and emulsion is then blended as it is sprayed into the pothole and covered with dry rock for immediate usability. (Materials: 1/4" dresser trap rock and asphalt emulsion oil: CRS-2 general purpose cationic rapid setting emulsion.)

Quotes requested for each category below: NEW CRACKS	Quote per Lineal Foot
If less than 2,000 lineal feet.	
If more than 2,000 lineal feet, but less than 5,000 lineal feet.	
If more than 5,000 lineal feet, but less than 10,000 lineal feet.	
If more than 10,000 lineal feet.	

Quotes requested for each category below: PREVIOUSLY FILLED CRACKS	Quote per Lineal Foot
If less than 2,000 lineal feet.	
If more than 2,000 lineal feet, but less than 5,000 lineal feet.	
If more than 5,000 lineal feet, but less than 10,000 lineal feet.	
If more than 10,000 lineal feet.	

Quotes requested for each category below: SPRAY PATCHING	Quote per Lineal Foot
If less than 2,000 lineal feet.	
If more than 2,000 lineal feet, but less than 5,000 lineal feet.	
If more than 5,000 lineal feet, but less than 10,000 lineal feet.	
If more than 10,000 lineal feet.	

ROADS TO BE DONE		
Road	Miles	Comment
Hardwood Lake Road	.75	Treat from Twin Lakes Drive to 3012 Hardwood Lake Road.
Homestead Road	.70	
Lyndhurst Bay Drive	1.00	
Magney Drive	1.40	

TOTAL PROJECT COST	
---------------------------	--

IV. CONTRACTOR SIGNATURE & CONTACT INFORMATION

Signature of Contractor

Date

Printed Name of Contractor

Telephone No./Email Address

Printed Address of Contractor