

<p>PERCH LAKE TOWNSHIP 2779 Big Lake Road, Cloquet, MN 55720</p>		<p><i>Gary Harms, Chair Keith Depre, Supervisor Steve Olson, Supervisor Cheri DeMenge, Treasurer Lora Eames, Clerk</i></p>
<p>perchlaketownship@gmail.com perchlaketownship.org 218-391-9178 (Clerk)</p>		

REQUEST FOR QUOTES
Watkins Spur Rebuild

The Perch Lake Township Board of Supervisors is requesting quotes for the Watkins Spur a Perch Lake Township road. The Watkins Spur Rebuild project will prepare the road for bituminous paving.

I. GENERAL INFORMATION:

- a. Rebuild Watkins Spur as outlined in attached plan.
- b. The successful Contractor will:
 - Provide specifications used if quote deviates from specification.
 - Be required to provide an insurance certificate verifying general liability insurance, a minimum of \$1.5 million per occurrence. (This insurance must cover all equipment operated for the work.)
 - Have a Tax ID No. (Federal Employer Identification or Social Security No.).
 - Have Workers compensation insurance if required, under Minnesota state law.
 - Successful contractor will have to provide a bond equal to 5% of project cost.
 - Be willing to sign "Indemnification, Hold Harmless and Defend Document" if quote is accepted.
 - The work must be completed no later than August 31, 2022.
- c. Contact for questions: Road Supervisor Steve Olson at (218-591-1795).

II. PROCESS:

- a. Quotes must be signed.
- b. Quotes can be mailed or emailed to Clerk Lora Eames at the address below 7:00 p.m. on Monday, February 14, 2022, before the regular monthly meeting of the Perch Lake Town Board.

SEND QUOTATION TO Perch Lake Township
 Attention Clerk Lora Eames
 2779 Big Lake Road, Cloquet, MN 55720
perchlaketownship@gmail.com or leames@perchlaketownship.org

- c. Supervisors reserve the right to delay a decision, negotiate with contractors regarding their proposals, or reject any and all quotes. The lowest quote will not be the only basis for consideration.

- d. Project drawings can be found on the Perch Lake Township website at [http://www.perchlaketownship.org/12-09-19 Drawings and Specs Signed 06-07-21.pdf](http://www.perchlaketownship.org/12-09-19%20Drawings%20and%20Specs%20Signed%2006-07-21.pdf) or go to perlaketownship.org, click on Documents & Policies to find all project information, including the RFQ Form.

III. PROPOSED COSTS:

Estimated Quantities

Specification Item	Unit	Total Estimated Quantities	Quote Amount
Mobilization	Lump Sum	1	
Relocate Building	Lump Sum	1	
Clearing and Grubbing	Lump Sum	1	
Remove Pipe Culverts	Lineal Feet	48	
Sawing Bituminous Pavement (full depth)	Lineal Feet	343	
Remove Bituminous Pavement	Square Yard	1462	
Select Granular Borrow (CV)	Cubic Yard	292	
Common Excavation	Cubic Yard	21	
Muck Excavation	Cubic Yard	189	
Soil Stabilization Geogrid	Square Yard	500	
Calcium Chloride Solution	Gallon	33	
Aggregate Base Class V	Ton	429	
Fine Aggregate Bedding	Cubic Yard	12	
Install 17" Span PC-CS Pipe Arch Culverts (Supplied by Perch Lake Township)	Each	8	
Random Riprap Class II	Cubic Yard	20.4	
Traffic Control Supervisor	Lump Sum	1	
Traffic Control	Lump Sum	1	
Erosion Control Supervisor	Lump Sum	1	
Culvert End Controls	Each	8	
Silt Fence; Type Hi	Lineal Feet	939	
Sediment Control Log Type Wood Fiber	Lineal Feet	739	
Filter Berm Type Natural Soils	Lineal Feet	739	
Rapid Stabilization Method 4 (Modified)	Square Yard	663	
Contingencies	Lump sum	1	
Total Project Cost			

IV. CONTRACTOR SIGNATURE & CONTACT INFORMATION

Signature of Contractor

Date

Printed Name of Contractor

Telephone No./Email Address

Printed Address of Contractor